

21

**OFFICE OF THE PRINCIPAL
PATNA COLLEGE**

ASHOK RAJ PATH
PATNA 800005

Phone No 0512-2678008, Web site: <https://patnacollege.ac.in/>

EMERGENT NOTICE INVITING QUOTATION

Quotation No: Pc/212

Date: 09/04/26

NAME OF WORK: CONSTRUCTION OF A LADIES TOILET NEAR DEPARTMENT OF MATHEMATICS, PATNA COLLEGE, PATNA

Sealed quotations are invited in prescribed format for this work, along with the amount of Earnest Money Deposit, as mentioned in the Terms and Conditions of this notice. For details terms and condition, please visit the office of the undersigned on any working days from 10.30 A.M. to 5.00 P.M. or website of College.

Designation of officer inviting quotation	Principal, Patna College, Patna
Place, Time & Date of receiving of quotation	Office of the Principal, Patna College, Patna up to 3.00 p.m. on 21.04.2026
Place, Time & Date of opening of quotation	Office of the Principal, Patna College, Patna at 3.30 p.m. on 21.04.2026

PRESCRIBED FORMAT

S.N.	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
1	P.M.R.	Providing electrical welding machine for spot welding for cutting existing grill gate for fixing door of proposed toilet, as per direction of engineer in charge.	1	Day	Day		
2	20.3 A.1	Making 25 cm (10") dia bore up to 4 mtr depth below ground with hand auger of approved quality in ordinary soil (vide classification of soil item A) true to plumb and without eccentricity in any stage of operation and disposal of the excavated earth up to 50 mtr, Lead in eluding all lifts, all complete as per approved design and direction of E/I	10	m	m		
3	2.28	Supplying and Filling in plinth with local sand and under doors including, watering, ramming consolidating and dressing complete.	3	Cum	Cum		
4	11.7 2.	Providing designation 100 A one brick flat soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification and direction of E/I,	12	Sqm	Sqm		
5	5.1. 2	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement-All work upto plinth level, 1:1:5:3(1 cement: 1.5 coarse sand:3 graded stone aggregate 20 mm nominal size)	2	Cum	Cum		
6	5.2. 2	Reinforced cement concrete work in wall (any thickness), including attached piasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts, etc. up to floor five level excluding cost of centring, shuttering, finishin and reinforcement. 1:1:5:3(1 cement: 1.5 coarse sand:3 graded stone aggregate 20mm nominal size)	1	Cum	Cum		

S.N.	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
7	5.3	Reinforced cement concrete work in beams,suspended floors, roofs having slope upto 15, landings,balconiec, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto floor five level excludingthe cost of centring, shuttering, finishing and reinforcement with 1:2:4(1 cement:2 coarse sand:4 graded stone aggregate 20 mm nominal size).	2	Cum	Cum		
8		Centring and shuttering including strutting,propping etc. and removal of form for.					
a	5.9.1	Foundations, footings, bases of columns etc. for mass concrete	8	Sqm	Sqm		
b	5.9.6	Columns,Pillars, Piers, Abutments, Posts and Struts	9	Sqm	Sqm		
c	5.9.3	Suspended floors, roots, landings, balcnies and access platform.	7	Sqm	Sqm		
d	5.9.5	Lintels, beams, plinth bams, griders, bressumers and contilevers.	11	Sqm	Sqm		
9		Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.					
a	5.22.1B	Mild steel 6.0 mm dia	31	Kg	Kg		
b	5.22.7A	Thermo-Mechanically Treated bars TMTC-500-8mm dia.	182	Kg	Kg		
10	6.1.1 4A	Brick work with bricks of class designation 100A in foundations and plinth in :Cement mortar 1:6 (1 cement: 6 coarse sand)	1.2	Cum	Cum		
11	6.18. 4A	Half brick masonry with bricks of class designation 100A in foundations and plinth in :Cement mortar 1:4 (1 cement: 4 coarse send)	38	Sqm	Sqm		
12	6.19 A	Extra for half Brick masonry in superstructure above pinth level upto floor V level	38	Sqm	Sqm		
13	4.1.2	Providing and laying in position cement concrete of specified grade exluding the cost of centring and shuttering-all work upto plinth level.	1	Cum	Cum		
14	13.1 7.1	12 mm cement plaster 1:3(1 cement: 3 coarse sand) finished with a floating coat of neat cement	11	Sqm	Sqm		
15	13.24 2	6 mm cement plaster to ceiling of mix :1:4(1 cement: 4 coarse sand	18	Sqm	Sqm		
16	11.3 9.	Providing and laying Ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturer) of 1 st quality conforming to IS : 13755 of NITCO , ORIENT , SOMANY , KAJARIA or equivalent make in colours such as white , Ivory , Grey , Fume , Red , Brown , laid on 20 mm thick cement motar 1:4 (1 cement: 4 Coarse sand) including grouting the joints with white cement and matching pigments etc, complete.	7	Sqm	Sqm		
17	11.3 6.	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS:15622 (Thickness to be specified by the manufacture) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	27	Sqm	Sqm		
18	13.11 2	Cement plaster in course sand 12 mm cement plaster of mix:1:4(1 cement :4 coarse sand)	43	Sqm	Sqm		
19	13.12 2	Cement plaster in course sand 15 mm cement plaster on rough side of single or half brick wall of mix:1:4(1 cement :4 coarse sand)	37	Sqm	Sqm		

P.K.H.J.K

S.N.	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
20	13.80 A.2	Providing and applying white cement based putty of average thickness 2 mm. of approved brand and manufacturer. over the plastered wall surface to prepare the surface even and smooth complete	98	Sqm	Sqm		
21	13.7 7.2	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including priming coat with cement primer	61	Sqm	Sqm		
22	13.4 6.1	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	37	Sqm	Sqm		
23		Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / aneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :					
a	21.1 .1.2	For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron)	7	Kg	Kg		
b	21.1 .2.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron)	7	Kg	Kg		
24	2631	Providing 4 mm thick A.C.P. of approved quality, as per direction of engineer incharge.	4	Sqm	Sqm		
25	9.10 0.2	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete:100 mm	4	No	Each		
26	9.97 .4	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with necessary screws etc. complete 150x10 mm	2	No	Each		
27	9.96 .2	Providing and fixing aluminium sliding door bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete 250x16 mm	2	No	Each		
28	9.48 .2	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings/ wooden frames with rawl plugs screws etc	47	Kg	Kg		
29	13.9 3.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:Two or more coats on new work	5	Sqm	Sqm		
30	17.1 .1	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low fixtures complete, including cutting and making good the walls and level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and floors wherever required .White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	1	No	Each		

PIC

S.N.	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
31	17.2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :W.C. pan with ISI marked white solid plastic seat and lid	1	No	Each		
32	17.7 .4	Providing and fixing wash basin of approved quality and design for fixing over slab as Counter Basin, as per direction of Engineer-in-charge.	1	No	Each		
33	17.2 8.1. 1	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Semi rigid pipe 32 mm dia	1	No	Each		
34	17.7 3.1	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. 450 mm long towel rail with total length of 495 mm, 78 mm wide and effective height of 88 mm, weighing not less than 170 gms	1	No	Each		
35	18.7 .3	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall 25 mm nominal outer dia Pipes	10	m	m		
36	18.8 .2	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge, Concealed work, including cutting chases and making good the walls etc 20 mm nominal outer dia Pipes	10	m	m		
37	18.2 1.2.1	Providing and fixing uplasticised PVC connection pipe with brass ions : 45 cm length 15 mm nominal bore	7	No	Each		
38	18.5	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms	1	No	Each		
39	18.5 3.	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS 8931	5	No	Each		
40	18.5 3A	Providing and fixing C.P. Brass extension nipple (size 15mmx50mm) of approved make and quality as per direction of Engineer-in-charge	8	No	Each		
41		Providing and fixing PTMT grating of approved quality and colour,					
a	18.58 .1.1	Circular type 100 mm nominal dia	3	No	Each		
b	18.58 .1.2	125 mm nominal dia with 25 mm waste hole	1	No	Each		
42	18.6 5.	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms	1	No	Each		
43		Providing and fixing on wall face unplasticised-PVC (working pressure 4 kgf per sqm) rain water pipes conforming to IS : 4985 including jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion.					

S.N.	Code No	Description	Quantity		Unit	Rate	Amount
a	12.78	75 mm diameter					
b		110 mm diameter	10	m	m		
44	12.78.2	Providing and fixing on wall face unplasticised -PVC molded fittings/accessories for unplasticised-PVC rain water pipes conforming to (S.4985 including jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion.	10	m	m		
a		75 mm bend					
b	12.79.5.2	110 mm bend	8	No	Each		
c	12.79.4.1	Single tee without door 75x75x75mm	4	No	Each		
d	12.79.4.2	Single tee without door 110x110x110 mm	3	No	Each		
45	P.M.R.	Providing 8 mm thick mirror of approved quality as per direction of engineer in charge.	2	No	Each		
46		Providing and fixing following materials of approved quality, as per direction of Engineer-in-charge.					
a		Hand Focet of approved quality	4	No	Each		
b		Two way Bib Cock of approved quality	2	No	Each		
47		Carriage of materials:					
a		Bricks from 8 Km distance of surface road with 1 Km kutcha road from P.U.	2900	No	%0No		
b		Stone aggregate from Manpur Gaya to P.U. Patna, 100 Km distance of surface road.	5	Cum	Cum		
c		Sone sand from Koelwar to P.U., Patna 45 Km distance of surface road.	7	Cum	Cum		
d		Local sand from 2Km distance of road and 1 Km distance of kutcha road.	3	Cum	Cum		
48		Price difference of materials					
a		Designation 100 A bricks	2900	No	%0No		
b		Cement	72	Bag	Bag		
49		Reserved price for any other unseen work.	1	L.S.	L.S.	4092	4092
		Total Amount					

Terms and conditions:

- 1 Xerox and self attested documents & Earnest Money Deposit in the form of Bank Draft in the favour of Principal, Patna College, Patna or N.S.C./ Time Deposit of Post Office, duly pledged in the name of Principal, Patna College, Patna @ 2% i.e.Rs.5,300/-are essentially required with quotations. Remaining amount of Security Deposits @ 8% of bill amount will be deducted from bill.
- 2 Work must be completed within 2 month after receiving work order.
- 3 Rate and amount of serial number 49 has been fixed as Rs.4092/- only.
- 4 Any registered agency of Government of Bihar / C.P.W.D. /M.E.S. will be considered.
- 5 Payment will be considered after satisfactory completion of work and after submitting satisfactory work completion certificate.
- 6 The undersigned reserve the right to accept or reject any or all the quotations without assigning any reason.
- 7 All disputes, what so ever shall be referred to the sole arbitration of the Principal, Patna College, Patna and his decision shall be final and binding on the agency.


 PRINCIPAL
 PATNA COLLEGE
 PATNA