

**OFFICE OF THE PRINCIPAL
PATNA COLLEGE**

ASHOK RAJ PATH
PATNA 800005

Phone No 0612-2678008, Web site: <https://patnacollege.ac.in/>

EMERGENT NOTICE INVITING QUOTATION

Quotation No 01/PC/2026

Date: 23/10/26

NAME OF WORK: INTERNAL REPAIR AND PAINTING OF DEPARTMENT OF PSYCHOLOGY, PATNA COLLEGE, PATNA.

Sealed quotations are invited in prescribed format for this work, along with the amount of Earnest Money Deposit, as mentioned in the Terms and Conditions of this notice. For details terms and condition, please visit the office of the undersigned on any working days from 10.30 A.M. to 5.00 P.M. or website of College.

Designation of officer inviting quotation Principal, Patna College, Patna

Place, Time & Date of receiving of quotation Office of the Principal, Patna College.
Patna up to 3.00 p.m. on 05.11.2026

Place, Time & Date of opening of quotation Office of the Principal, Patna College.
Patna at 3.30 p.m. on 05.11.2026

PRESCRIBED FORMAT

S.N	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
1	14.1.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement :4 fine Sand)	93	Sqm	Sqm		
2	13.80	Removing dry or oil bound distemper by scrapping, sand paper and preparing the surface smooth including necessary repari scratches etc. complete.	867	Sqm	Sqm		
3	13.80 A.2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. Applying one coat of cement primer of approved brand and manufacture on wall surface.	200	Sqm	Sqm		
4	13.77.2	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade - New work (two or more coats) over and including priming coat with cement primer	200	Sqm	Sqm		

S N	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
5	13.77 A.1	Distemping with 1st quality washable distemper (ready made) of approved manufacturer and of required shade and colour complete. As per manufacture's specifications. Two or more coats on new work	760	Sqm	Sqm		
6	13.81 .3	Applying priming coat: With ready mixed zinc chromate yellow primer of approved brand and manufacture on steel galvanized iron/steel works	50	Sqm	Sqm		
7	13.93 .2	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: One or more coats on old work.	206	Sqm	Sqm		
8	10.1	Structural steel work in singal section fixed without connecting plate including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all comple.	100	Kg	Kg		
9		Providing following workers and materials of approved make for inserting steel beams fro strengthening of roof and other related works. As per direction of Engineer In-charge.					
a	o123	Mason (for orick work) 1st class	4	Day	Day		
b	OL71	Skilled Labour	14	Day	Day		
10	18.7. 5	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall- 40 mm nominal outer dia Pipes	5	m	m		
11	17.28 1.2	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Semi rigid pipe 40 mm dia	2	No	Each		
12	15.41	Dismantling cement asbestos, Celotax or other hard board ceiling or partition walls including stacking of serviceable materials and disposal of unserviceable materials within 50 metres lead.	41	Sqm	Sqm		

Plat
12-10-26

S N	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
13		Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on interlocking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x 1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanized butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.					
		8mm thick fully perforated calcium silicate board made with Calcareous & Siliceous materials reinforced with cellulose fiber manufactured through autoclaving process to give stable crystalline structure with minimum compressive strength 225 kg / sq. cm, bending strength 100kg/sq. cm, of size 595x595 mm, having perforation of dia. 10 mm with minimum perforated area 18 % with non woven tissue on the back side, having an NRC(Noise Reduction Co efficient) of 0.85, with 50 mm thick rock wool of 48 kg /cum backing.	41	Sqm	Sqm		
	P.M. R.	Less, for using old materials of existing false ceiling to be removed, as per direction of Engineer In-charge.	41	Sqm	Sqm		
	S.O. R.	Carriage of materials: Sone sand from Koelwar, 45 Km distance of surface road from site.	2	Cum	Cum		
	S.O. R.	Price difference of materials for Patna urban area: Cement	11	Bag	Bag		


P.K. Singh
12-10-20

16

N	Code	Description	Quantity		Unit	Rate	Amount
	No					(Rs.)	
17		Reserved price for any other unseen work.	1	L.S.	L.S.	5733	5733
		Total Amount					

TERMS & CONDITIONS:

- 1 This Quotation Notice is available on the website of Patna College, Patna and may be downloaded.
- 2 Xerox and self attested documents & Earnest Money Deposit in the form of Bank Draft in the favour of Principal, Patna College, Patna or N.S.C./ Time Deposit of Post Office, duly pledged in the name of Principal, Patna College, Patna @ 2% i.e. Rs.3,800/- are essentially required with quotations. Remaining amount of Security Deposits @ 8% of bill amount will be deducted from bill.
- 3 Self attested copies of Registration certificate, Registration Certificate of G.S.T., PAN card along with Experience certificates are required with quotations.
- 4 Work must be completed within 2 month after receiving work order.
- 5 Rate and amount of serial number 17 has been fixed as Rs.5733/- only.
- 6 Any registered agency of Government of Bihar / C.P.W.D. /M.E.S. will be considered.
- 7 Payment will be considered after satisfactory completion of work and after submitting satisfactory work completion certificate.
- 8 The undersigned reserve the right to accept or reject any or all the quotations without assigning any reason.
- 9 All disputes, what so ever shall be referred to the sole arbitration of the Principal, Patna College, Patna and his decision shall be final and binding on the agency.


 22/10/26
PRINCIPAL
PATNA COLLEGE
PATNA
 Patna College, Patna