

17/

18/

**OFFICE OF THE PRINCIPAL
PATNA COLLEGE**

ASHOK RAJ PATH
PATNA 800005

Phone No 0612-2678008, Web site: <https://patnacollege.ac.in/>

EMERGENT NOTICE INVITING QUOTATION

Quotation No 02/PC/2026

Date: 23/10/26

**NAME OF WORK: CONSTRUCTION OF SHADE IN FRONT OF POLICE T.O.P IN THE CAMPUS OF
PATNA COLLEGE, PATNA**

Sealed quotations are invited in prescribed format for this work, along with the amount of Earnest Money Deposit, as mentioned in the Terms and Conditions of this notice. For details terms and condition , please visit the office of the undersigned on any working days from 10.30 A.M. to 5.00 P.M. or website of College.

Designation of officer inviting quotation Principal, Patna College, Patna

Place, Time & Date of receiving of quotation Office of the Principal, Patna College,
Patna up to 3.00 p.m. on 05.11.2026

Place, Time & Date of opening of quotation Office of the Principal, Patna College,
Patna at 3.30 p.m. on 05.11..2026

PRESCRIBED FORMAT

S.N.	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
1	2.28.	Supplying and Filling in plinth with local sand and under floors including, watering, ramming consolidating and dressing complete.	2.3	Cum	Cum		
2	11.72	Providing designation 100 A one brick flat soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification and direction of E/I,	25	Sqm	Sqm		
3	4.1.2	Providing and laying in position cement concrete of specified grade exluding the cost of centring and shuttering-all work upto plinth level- 1:1.5:3(1 Cement :1.5 coarse sand:3 graded stone aggregate 20 mm nominal size)	2	Cum	Cum		
4	16.89.	Providing and laying matt finished vitrified tiles of size300x300x9.8mm having water absorption less than 0.5% and conforming to IS: 15622 of approved make in all colours and shades in outdoor floors such as footpath, court yard, multi modals location etc., laid on 20mm thick base of cement mortar 1:4 (1 cement : 4 coarse sand) in all shapes & patterns including grouting the joints with white cement mixed with matching pigments etc. complete as per direction of Engineer-in-Charge.	26	Sqm	Sqm		

S N	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
5	2 8	Earthwork in excavation in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	1.2	Cum	Cum		
6	5 1 2	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement- All work upto plinth level. 1:1.5:3 (1 cement: 1.5 coarse sand: 3 graded stone aggregate 20 mm nominal size)	0.7	Cum	Cum		
7	5.9.5	Centring and shuttering including strutting, propping etc. and removal of form for Lintels, beams, plinth bams, grids, bressumers and cantilevers.	5.1	Sqm	Sqm		
8	5 22.7 A	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated bars TMTC-500-8mm dia.	45	Kg	Kg		
9	6.1.12/1	Brick work with bricks of class designation 100 A in foundations and plinth in : Cement mortar 1 : 4 (1 cement: 4 coarse sand)	1	Cum	Cum		
10	13.11.2	12 mm cement plaster of mix: 1:4 (1 cement : 4 coarse sand)	16	Sqm	Sqm		
11	13.26	Neat cement punning	16	Sqm	Sqm		
12	11.23.2	Marble stone flooring with 18 mm thick marble stone (sample of marble shall be approved by Engineer - in- charge) over 20 mm (average) thick base of cement mortar 1:4 (1 cement: 4 coarse sand) laid and jointed with grey cement slurry including rubbing and polishing complete with: Rajnagar plain white marble 18mm thick above 0.10 sqm upto 0.20 sqm	6	Sqm	Sqm		
13	10.1	Structural steel work in singal section fixed without connecting plate including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	300	Kg	Kg		
14	10.16.2	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete- Hot finished seamless type tubes	200	Kg	Kg		

S.N.	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs)	
15	12.65X.2	Providing & fixing at all heights, levels and locations colour finish Aluminium alloy roofing sheets of alloy IS designation 31500, temper H x 8 conforming to IS 737 and dimensions as per IS code 2676 with characteristics of good formability and corrosion resistance. The profile sheets shall be fixed to truss members in slope or required pitch or curvature with Hex cap headed self drilling / tapping Stainless steel screws M6, 60 mm long with 3 mm EPDM seal washer etc. all inclusive of labour, scaffolding, T&P and sundries etc. complete as per directions of the Engineer-In Charge. {Cost of truss/frame work shall be paid separately}. 0.71 mm, Aluminium Color coated troughed profile with center to center pitch of 200 mm, depth of 32 mm, overall profile width 1092 mm, cover width 1000mm.	28	Sqm	Sqm		
16	13.81.3	Applying priming coat: With ready mixed zinc chromate yellow primer of approved brand and manufacture on steel galvanized iron/steel works	50	Sqm	Sqm		
17	P.M.R.	Providing Electrical welding machine for spot welding, as per direction of Engineer In-charge.	1	Day	Day		
18	13.93.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	100	Sqm	Sqm		
19		Carriage of materials:					
a		Designation 100 A Bricks from 8 Km distance of surface road and 1 Km lead of kutcha road.	1170	No	%0No		
b		Stone aggregate from Manpur, Gaya 100 Km distance of surface road from site.	2.6	Cum	Cum		
c		Sone sand from Koelwar, 45 Km distance of surface road from Site.	3	Cum	Cum		
d		Local sand from 3 Km distance including 1 Km lead of kutcha road from site.	2.4	Cum	Cum		
20		Price difference of materials for Patna urban area.					
a		Cement	30	Bag	Bag		

Plt
12-10-28

S N	Code	Description	Quantity		Unit	Rate	Amount
	No					(Rs.)	
21		Reserved price for any other unseen work.	1	L.S.	L.S.	9081	9081
		Total Amount					

TERMS & CONDITIONS:

- 1 Xerox and self attested documents & Earnest Money Deposit in the form of Bank Draft in the favour of Principal, Patna College, Patna or N.S.C./ Time Deposit of Post Office, duly pledged in the name of Principal, Patna College, Patna @ 2% i.e.Rs.3,900/-are essentially required with quotations. Remaining amount of Security Deposits @ 8% of bill amount will be deducted from bill.
- 2 Self attested copies of Registration certificate, Registration Certificate of G.S.T., PAN card along with Experience certificates are required with quotations.
- 3 Work must be completed within 2 month after receiving work order.
- 4 Rate and amount of serial number 21 has been fixed as Rs.9081/- only.
- 5 Any registered agency of Government of Bihar / C.P.W.D. /M.E.S. will be considered.
- 6 Payment will be considered after satisfactory completion of work and after submitting satisfactory work completion certificate.
- 7 The undersigned reserve the right to accept or reject any or all the quotations without assigning any reason.
- 8 All disputes, what so ever shall be referred to the sole arbitration of the Principal, Patna College, Patna and his decision shall be final and binding on the agency.

Prin
23/10/26
PRINCIPAL
PATNA COLLEGE
PATNA